

BRUHAT BANGALORE MAHANAGARA PALIKE
DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division
SCHDULE-B

Name of Work: Improvements to roads and drains at between 3rd main & 4th main cross roads Manjunatha Nagara in Ward no 14 (Bagalagunte)

Sl	Description of Work	Unit	Qty	Sanctioned Rates	
				In figures (Rs)	In Words (Rs)
1	2	3	4	5	6
1	Excavation for road, drains and similar works - KSRRB 300-1. Earthwork excavation by manual means in Ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.	Cum	734.40	86.92	Rupees Eighty six & Ninty Two Paise Only
2	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180 kgs. with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth. including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	51.00	5159.02	Rupees Five Thousand One hundred Fifty Nine & Two Paise Only
3	Providing and removing centering , shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications.	Sqm	1360.00	310.58	Rupees Three hundred ten & Fifty Eight Only
4	Design mix M20 with OPC cement @ 320kgs. with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @ 0.46cum, with superplastiser @3lts confirming to IS9103-1999 Reaffirmed-2008- i) Upto 5 m height.	Cum	127.50	6965.26	Rupees Six thousand nine hundred Sixty Five & Twenty Six Only
5	Supplying, fitting and placing TMT bar Fe 500 reinforcement in sub-structure complete as per drawing and Technical Specifications complete as per specifications	Tonne	8.43	66482.14	Rupees Sixty Six thousand four hundred Eighty two & Fourteen Only


EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Signature of the Contractor


Executive Engineer

6	Supplying and fixing precast reinforced concrete slab 10cm thick including cost of reinforcement as per design and drawing material cost transportation hire charges of machinery machine cutting the vertical face to get plain even surface etc complete with all leads and lift conveyance charges labour charges inclusive of cost of all materials	Sqm	255.00	1698.00	Rupees One thousand Six hundred Ninety Eight Only
7	Providing laying spreading and compacting graded stone aggregates to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site laying in uniform layers with paver in sub base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications Specification No. 406 with all leads and lifts etc complete as per the direction of Engineer-in-charge of the work	Cum.	142.80	1768.08	Rupees One thousand Seven hundred Sixty Eighty & Eight Paise Only
8	Construction of dry lean cement Concrete mix CC1:5:10 with OPC cement @160kgs, with 25mm and down size graded granite metal coarse aggregate at 0.86cum and fine aggregates @ 0.58cum sub-base over a prepared sub-grade with (Coarse and fine aggregate conforming to IS 383) aggregate cement ratio not to exceed 15:1. Aggregate gradation after blending to be as per Table 600-1, cement content not to be less than 160kg/cum, optimum moisture content to be determined during trail length construction, concrete strength not to less than 10Mpa at 7 days, mixed in a batching plant, transported to site, laid with a paver with electronic sensor, compacting with 8-10 tonnes vibratory roller, finishing and curing complete as per specifications	Cum	142.80	3986.66	Rupees Three thousand Nine hundred Eighty Six 7 Sixty Six Paise Only
9	Cement concrete pavement Construction of un-reinforced plain cement concrete pavement, thickness as per design, over a prepared sub base with OPC cement or any other type as per clause 1051.2.2 with 25mm and down size graded granite metal coarse aggregates and fine aggregates, with superplasticiser @3lts conforming to IS9103-1999 Reaffirmed F2008, mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing) Spreading the concrete with shovels, rakers compacted using needle, screed and plate vibrator and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades as per drawing complete as per specifications. M30 (at 360Kg per cum coarse aggregate @ 0.69cum and fine aggregate @ 0.43cum)	Cum	142.80	6217.96	Rupees Six thousand Two hundred Seventeen & Ninty Six Paise Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Signature of the Contractor

Executive Engineer

10	Vacuum de-watering with vacuum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator, HOM of machinery screed vibratory power Floater blade and disc etc. with all lead and lift	Sqm	952.00	95.40	Rupees Ninty Five & Forty Paise Only
11	Providing groove cutting to concrete pavement for width of 5mm to 10mm and depth 80mm - 100mm including cost of cutting machine, generator & HOM of machinery including cost of blade, coolant, etc. including cleaning of grove & providing sand and hot bitumen fillars, and filler metal etc. including cost of conveyance of all amterials, labour, lead and lift charges and all other incidental charges as per drawing and as per specifications	Mtr	61.60	121.90	Rupees One hundred twenty One & Ninty Paise Only
12	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17 4/KSRRB : M100-4 1 Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading	Cum	734.40	85.65	Rupees Eighty Five & Sixty Five paise Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Signature of the Contractor

Executive Engineer

Signature of the Contractor

Executive Engineer